BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/RD/WORK_INDENT28391

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/14/2017-18, Date:01.01.2018

Package-6, includes 3 works of Rs.100.00 lakhs

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of D NARAHARI	
				In Figures	In Words
1	827.58	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification.	Cum	201.65	Rupees Two Hundred One and Sixty Five Paise Only
2	2123.79	Removing & Refixing Stone slabs of drains and Pointing in C.M(1:3)	Sqm	86.91	Rupees Eighty Six and Ninety One Paise Only
3	1198.11	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 7.5cms thick	Sqm	718.14	Rupees Seven Hundred Eighteen and Fourteen Paise Only
4	115.32	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5770.24	Rupees Five Thousand Seven Hundred Seventy and Twenty Four Paise Only
5	57.6	Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	5735.98	Rupees Five Thousand Seven Hundred Thirty Five and Ninety Eight Paise Only
6	522.5	KSRRB M300-14. Excavation for roadwork in soil with hydraulic excavator of 0.90 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to embankment location and complete as per specifications.	Cum	160.48	Rupees One Hundred Sixty and Forty Eight Paise Only
7	407.6	KSRRB M400-6.2: Construction of granular sub-base by providing Close graded material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with mortar grader on prepared surface and compacting with vibratory roller to achieve the desired density, complete as per specifications. A Plant Mix methad For Grading II Material	Cum	1796.48	Rupees One Thousand Seven Hundred Ninety Six and Forty Eight Paise Only
8	615.21	KSRRB M 400-17, Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechaniqal mix plant carriage ' of mixed Material by tipper to site, laying in uniform layers with paver in sub- base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density.complete as per specifications.	Cum	1907.40	Rupees One Thousand Nine Hundred Seven and Forty Paise Only
9	2497.6	KSRRB M 500-6, Providing and applying primer coat with SS bitumen emulsion on prepared surface of granular Base such as WBM WMM including clearing of road surface and spraying primer at the rate of 0.60 kglsqm using mechanical means complete as per specifications.	Sqm	32.02	Rupees Thirty Two and Two Paise Only
10	3272.5	KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatement including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	3.43	Rupees Three and Forty Three Paise Only
11	5310.5	KSRRB M500-7 : Providing and applying tack coat using 80/100 grade bitumen (VG10) on prepared black topped surfaces at 2.5 Kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	13.72	Rupees Thirteen and Seventy Two Paise Only

For Benaka Developers And Projects Pvt. Ltd

NARAHARI .D
Managing Director

Signature of the contractor

14/12

Executive Engineer

	ved ty.	Description	Unit	Approved Tender Rates of D NARAHARI	
				In Figures	In Words
12	212.42	KSRRB M500-19. Providing and laying bituminous concrete 30-40 mm compacted thickness with VG30 Bitumen grade using 40-60 HMP using crushed aggregates of grading II, premixed with bituminous binder at 5.4% of mix and filler, transporting the hot mix to work site, laying with a mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification clause No. 500.9 complete in all respects as per specifications. MORTH Specification No. 509	Cum	8645.07	Rupees Eight Thousand Six Hundred Forty Five and Seven Paise Only
13	233.38	KSRRB M800-13. Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications.	Sqm	585.49	Rupees Five Hundred Eighty Five and Forty Nine Paise Only
14	291.2	KSRB 5.2-3: Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as per specifications.	Cum	4787.95	Rupees Four Thousand Seven Hundred Eighty Seven and Ninety Five Paise Only
15	516.8	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications.	Sqm	1037.18	Rupees One Thousand Thirty Seven and Eighteen Paise Only
16	631.98	KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	110.92	Rupees One Hundred Ten and Ninety Two Paise Only
17	84.22	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	6221.94	Rupees Six Thousand Two Hundred Twenty One and Ninety Four Paise Only
18	300	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	1960.18	Rupees One Thousand Nine Hundred Sixty and Eighteen Paise Only
19	556	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc.,	Sqm	357.92	Rupees Three Hundred Fifty Seven and Ninety Two Paise Only
20	87.5	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8	Sqm	68.61	Rupees Sixty Eight and Sixty One Paise Only

For Benaka Developers And Projects Pvt. Ltd

Signature of the Contractor
NARAHARI .D
Managing Director

14/12

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

14/12